

Foundation Budget

Gazebo Foundation Example | Palo Cedro area, California | 2026-09-16 | USD

DE-IDENTIFIED HISTORICAL EXAMPLE - NOT CURRENT PRICING

Item	Estimate
Net concrete quantity	12.69 yd3 (9.70 m3)
Including waste (+8%)	13.71 yd3 (10.48 m3)
Budgeted concrete order	14.00 yd3 (10.70 m3)
Ready-mix concrete	14 yd3 x USD 230.00/yd3 = USD 3,220.00
Burdened labor	160 h x USD 65.00/h = USD 10,400.00
Direct construction cost	USD 22,620.00
Complete foundation budget	USD 29,134.56
Low / high scenarios	USD 19,620.15 - USD 45,110.48

Included scope

Slab, perimeter beams, six pedestals/enlarged footings, rear curb and fireplace foundation allowance; ordinary excavation/haul-off, backfill/compaction, reinforcing, formwork, embeds, pumping, labor, base, basic drainage/joints and cleanup.

Drawing basis

De-identified example based on a two-sheet gazebo plan (A1/S1), retaining the historical estimate numbers. Customer identity/address and source drawings are omitted. Inspect the actual drawings for each new project.

De-identified historical example. Rates are unquoted estimating allowances from the original estimate, not current prices or fixed bids.

Sales/use tax has not been added. Confirm local taxes and what supplier quotes include.

Concrete Quantities

Gazebo Foundation Example | Palo Cedro area, California | 2026-09-16 | USD

Item	Basis / formula / source	Net yd3
4 in slab	Full gross area, approximately 506.7 sq ft. $25.333333 * 20 * 4 / 12 / 27$ [Derived] A1/S1 plans and slab notes	6.26
Perimeter beams: net addition	Exclude counted slab; 12 in below base plus assumed 4 in connection. $84 * 1 * (12 + 4) / 12 / 27$ [Allowance] S1 Detail 3/plan; 84 ft and connection are assumptions	4.15
Six pedestals: net addition	Assume 3 ft square x 12 in footings; deduct beam/slab overlaps. $6 * ((3 * 3 - 3) * 1 + (2.666667 * 2.666667 - 2.666667 * 1) * 4 / 12 + 2.666667 * 2.666667 * 2 / 12) / 27$ [Allowance] S1 Detail 2; full footing dimensions missing	1.93
Rear curb	20 ft clear, 6 in wide, 2 in above slab. $20 * 0.5 * 2 / 12 / 27$ [Allowance] S1 Detail 1; minimum upstand assumption	0.06
Fireplace allowance	Net foundation addition only; fireplace masonry excluded. 0.3 [Unconfirmed] S1 central feature; dimensions incomplete	0.30
Net concrete quantity		12.69
Budgeted concrete order	8% waste	14.00

Assumptions and unresolved dimensions

- 84 ft is an estimated centerline length. The assumed 4 in connection adds about 1.04 yd3; deduct if not required. It is not a confirmed total depth.
- 3 ft square pads are not fully dimensioned on the plan. Deduct an assumed 3 sq ft beam overlap each; verify pedestal elevations and fireplace footing.
- Assumes ordinary soil and normal access; terrain, rock and pool/paving repairs are unverified.

Materials, Labor & Total Cost

Gazebo Foundation Example | Palo Cedro area, California | 2026-09-16 | USD

Item	Low	Base	High
Ready-mix concrete	2,520.00	3,220.00	4,160.00
Burdened labor	7,040.00	10,400.00	15,600.00
Rebar and foundation embeds	1,000.00	1,500.00	2,300.00
Formwork materials / rental	600.00	900.00	1,400.00
Base and moisture-control allowance	700.00	1,000.00	1,500.00
Pump and mobilization extras	1,000.00	1,500.00	2,400.00
Excavation, hauling, backfill, compaction	1,800.00	2,800.00	4,500.00
Drainage, joints, adjacent protection	500.00	800.00	1,400.00
Curing, sawcutting consumables, cleanup	350.00	500.00	850.00
Direct construction cost	15,510.00	22,620.00	34,110.00
Contractor overhead / profit (10% / 12% / 15%)	1,551.00	2,714.40	5,116.50
Contingency (15% / 15% / 15%)	2,559.15	3,800.16	5,883.98
Complete foundation budget	19,620.15	29,134.56	45,110.48

Amounts are rounded to cents for display; calculations use unrounded values. Contingency applies to direct cost plus overhead/profit. Taxes are not added by the calculator; see the project tax note.

Sales/use tax has not been added. Confirm local taxes and what supplier quotes include.

Rates and allowance basis

Low/base/high rates: USD 210/230/260 per yd3, provisionally including standard delivery; pump and mobilization extras separate.

Rebar and foundation embeds: Approx. 0.20-0.35 metric tonnes including waste; not a bar schedule. Foundation anchors included.

Formwork materials / rental: Installation/stripping labor is in the labor schedule.

Base and moisture-control allowance: Allow 7-8 yd3 aggregate; moisture materials provisional, vapor barrier not explicitly specified.

Pump and mobilization extras: Assume 1-2 visits, including pump operator.

Excavation, hauling, backfill, compaction: Equipment subcontract includes operators/ordinary disposal; earthwork and haul distance unmeasured.

Drainage, joints, adjacent protection: Materials/protection consumables; labor counted separately.

Curing, sawcutting consumables, cleanup: Ordinary consumables/cleanup, not special inspections.

Labor & Verification

Gazebo Foundation Example | Palo Cedro area, California | 2026-09-16 | USD

Item	Labor-hours	Base labor cost
Layout, base and coordination	24	1,560.00
Forms and pedestals	48	3,120.00
Rebar and embeds	24	1,560.00
Place, vibrate and finish	40	2,600.00
Strip, cure, sawcut, clean	16	1,040.00
Drainage, joints, protection	8	520.00
Burdened labor	160	10,400.00

Labor includes wages and employer burden. Excavation and pump subcontract allowances include their operators; do not count them again here. Overall overhead/profit is separate. Worker-days use 8 hours; inspections and curing extend calendar duration.

Low: 128 h x USD 55.00/h; High: 208 h x USD 75.00/h.

Verify before quoting / ordering

1. Reconcile filename, project identity, address and approved drawing set.
2. Confirm pedestal footing dimensions, beam depth, rear wall height, fireplace load/footing and detail-to-plan mapping.
3. Confirm concrete strength, reinforcement, embeds, slopes/outlets, pump reach and access.

Scope limits

1. Timber superstructure, roof, finishes, fireplace/kitchen equipment, countertop masonry, pool, extra patios and underground services excluded.
2. Design/permits, special inspections, rock, unsuitable-soil replacement, shoring/dewatering and extensive existing-facility repairs excluded.